




Coronado USD Feasibility Assessment for Solar PV & Battery Energy Storage Summary of Findings

January 16, 2020



Findings Report Summary Presentation

Overview of Feasibility Study Process

Summary of Site Assessments

Proposed Projects – Solar PV & Energy Storage

Projected Economics

Conclusions & Next Steps for Consideration

Project Schedule



Feasibility Study Process

- Electricity Use & Billing Analysis – 9 SDG&E Meters
- Baseline Time of Use (TOU) Rate Analysis
- Demand Profile Analysis (for Battery Energy Storage)
- Initial Solar PV System Sizing
- Site Audits
 - Area Availability/Constraints & Logistics for Solar PV
 - Electrical Infrastructure & Utility Infrastructure Assessment
- Interconnection Evaluation
- Project type options (rooftop, carport, shade canopy, ground)
- Adjust system sizes for site audit results
- Initial solar array layouts
- Project cost estimates & PPA rates
- Battery Storage Integration, as applicable
- Rate optimization (for post project installation assumptions)
- Financial cash flow proformas & projected net savings

Feasibility Study Results - Projects

	Interconn.	System	Consumption	Current	Proposed	Battery	Demand (kW)	
Site	Tariff	Size (kW dc)	Offset (%)	Rate	Rate	Size (kWh)	Offset (%)	Notes
Crown Preschool	NEM	53	77%	AL-TOU	DG-R			Shade Canopy
Village Elementary	NEM	175	84%	AL-TOU	DG-R	60	47	Roof & Shade Canopy
Silver Strand Elementary	NEM	100	81%	AL-TOU	DG-R			Shade Canopy
Coronado High School	NEM	197	28%	AL-TOU	DG-R	120	38	Roof & Shade Canopy
Coronado HS Stadium				AL-TOU		120	36	Site Constraints
Aquatics Complex				AL-TOU		60	24	Site Constraints
Coronado Middle School				AL-TOU				Site Constraints
District Offices				AL-TOU				Site Constraints
Total NEM Projects Size:	NEM	525	48%					
Hypothetical Alternate	N/A	1,100	63%	DG-R	RES-BCT			Ground Mount

An aerial photograph of a vast solar farm. The image shows numerous rows of solar panels, which appear as a grid of dark blue and black rectangles. A dirt road or path runs diagonally through the center of the panel arrays, separating them into two main sections. The panels are tilted at an angle, and the overall layout is highly organized and repetitive.

An aerial photograph of a vast solar farm. The image shows numerous rows of solar panels, which appear as a grid of dark blue and black rectangles. A dirt road or path runs diagonally through the center of the panel arrays, separating them into two main sections. The panels are tilted at an angle, and the overall layout is highly organized and repetitive.

Conclusions & Next Steps

- Solar + Battery Storage project (4 NEM sites, 2 with battery storage systems) provides greatest savings potential & payback performance.
- Cash Purchase yields greater savings & ROI than PPA financing.
- Standalone Battery Energy Storage at Coronado HS Stadium and Aquatics Center provide added savings.
 - Reduces the Demand Charge component costs.
- If the District owned or leased property to support an export tariff project option (RES-BCT), greater overall savings could be achieved (greater than NEM projects).
 - 1MW ground-mount project would require 3-4 acres
- Next Steps:
 - Consider/evaluate financing options
 - Run RFP process to test the market
 - Ask for PPA & EPC price options



Project Schedule

- Develop RFP docs, project specs & 30% design: 4wks
- RFP process, evaluate proposals, select vendor: 4wks
- Contract Negotiations: 3wks
- 4217 Code resolution, Board Approval: 2wks
- Vendor due diligence & design/engineering: 8-10wks
- DSA Design approval and permitting: 4-6wks
- Construction / Installation: 16-20wks
- Commissioning and PTO: 3wks
- Startup, performance validation, project close out: 3wks

- Total: 10 to 12 months



Kevin Ross
TerraVerde Energy, LLC
949-212-6555
Kevin.ross@terraverde.energy

TerraVerde
ENERGY